

Specification

Name of work Place of work (region). Amount rub.

Keeping in combat readiness and repair water systems, including:

1. Replacement of technological pipelines and ZRA technical water (Lab):

- Fault detection system of technical water supply:

- Trumpet d108mm - 98m;

- Trumpet d80mm - 165m;

- Pipe d 133mm - 230m;

ZRA:

- D 100mm - 6 pcs;

- D 80mm - 12p;

- D 150mm - 10 pieces;

CD-9 - 4 pcs.

Penza region. (A / h 34011)

Replacement of pipelines, ZRA system of technical water supply:

Dismantling the pipeline D = 159 mm - 200 lm

Installation of the pipeline D = 159 mm - 200 lm

Dismantling of valve D = 150 mm - 2 pcs.

Installation of a ball D = 150 mm - 2 pcs.

Dismantling of pipe insulation (fiberglass) - 150 m2.

Dismantling of pipe insulation (mats) - 3,9 m3. Mounting supporting structure - 0,2 t.

Ogruntovka metal surfaces at a time primer - 100 m2.

Ogruntovka metal surfaces at once varnish - 200 m2.

Insulation of pipelines mats and canvases of the super fiber - 5 m3.

Covering the surface insulation foil Aluminum - 163 m2.

Wrapping the surface insulation rolled materials - 163 m2.

Descent, moving materials to the installation site (distance 2500 m) - 12 tons

Moscow region. (A / h 33877)

1. Repair of technical water supply:

- Replacement of the pump 6NDV-B - 1 piece;

- Replacement SDV-80/18 - 2 pcs.;

- Replacement of 2,5 NF - 2 pcs.

- Replacement of pipes D = 80 mm - 1000 m;

- Replacement of valves, including:

valve D = 200 mm - 4 pcs.;

- D = 150 mm - 6 pcs.;

- D = 100 mm - 10 pcs.,

- D = 80 mm - 20 pcs.;

back. Valves:

- D = 200 mm (vertical) - 1 pc.

- D = 150 mm - 4 pcs.;

- D = 100 mm - 2 pcs.;

- D = 80 mm - 2 pcs.;

- D = 50 mm - 1 pc.

Moscow (A / h 25776)

Replacement of pumping installation BY 5 / 30: - dismantling and assembling BY 5 / 30;

- Replacement of pipes d50mm - 10m,
- Replacement ZRA d 50mm - 8pcs/Repair reservoir (20 m3):
- Cleaning and welding inside the tank (area 48m2) /hydraulic test tank/Repair of tower PRT - 600: -
- Removal and installation of fans SH - 25;
- Removal and installation of nozzles;
- Installation of scatterers/Repair of artesian wells:
(Disassembly and reassembly of the pump unit 1ETSV 8-25-100, checking debit).

Kaluga region. (A / h 92628)

Replacement of pipelines and ZRA technical water supply:

- Excavation work on the trench (1000 m);
- Replacement of pipe d 108mm ~~000m~~ 1; 1000m

ZRA:

- DN 100 mm - 4 pcs;
- Priming and painting of pipes;
- Hydraulic testing of pipelines.

} - je digi up + replace
1000m of pipe

Moscow region. (A / h 52617)

Total: