

33877

Kuznetsk-8 Lot 1 Repair air conditioning system

Replacement and commissioning conditioner CD - 50
Dostvka equipment to the installation site-4, 6 m;
Replacing the air conditioner;
Zamnavozduhovodov d = 885 mm - 40 m2;
Replacement air d = 660 mm - 200 m2;
Replacing pipes d = 150 mm - 90 m;
Replacement of valves (valves) d = 150 mm - 2 pcs., painting, pipe insulation;
Stem DSWD, dismantled equipment - 4,7 m.

Lot 2 Repair of building structures

Replacing ceramic tile floor - 370 m2;
Stained floors, walls - 13,340 m2; #
Plastered walls and ceilings - 1460m2;
Coverage linoleum - 125 m2;
Repair toilets:
Replacing ceramic tile floor - 100 m2;
Replacing ceramic tile walls - 450m2;
Replacing urinals - 6 pc;
replacement shells - 13 pieces;
Replacing toilets - 14;
Replacement kanazizatsionnyh pipes d = 50 mm - 10 m;
Replacement kanalizachionnyh pipes d = 150 mm - 20 m;
Replacing water pipes d = 20 mm - 14 m;
Replacement of water supply pipelines d = 25 mm - 28 m;
disassembling, assembling: Cable Lighting - 80 m;
Lamps - 12 pcs;
switches - 6 pcs.

Lot 3 Repair of building structures and air-conditioning system

Repair of air conditioning systems:
Dismantle the air units (KTH) - 14 pcs;
dismantling fittings flange with manual d = 40mm - 16 pcs;
removal of pipes d = 57 mm - 140 m;
trezhpolyusnyh Dismantling machines to be installed on the floor on the current to 400 A - 14 units;
Dismantling cable 4.2 veined with mounting brackets naklanyami - 280m;
Dismantling of cable steel structures 0.18 m.
Dismantling of vertical earthing - 14sht;
Mounting steel structures (the ground under the KTN) - 0,45 tons;
installation of air units - 9 units.; Piping d = 57 mm - 90 m;
mounting flange valve with manual drive d = 50mm - 18units;
Installation three-pole machines, ustanavliemyh floor NP current to 400A - 9 pieces, assemble the cable conductor with a 4.2 mount overhead straps - 146m;
Cabling steel structures - 0,11 tons;
Installation of earthing vertical round steel d = 12mm - 9 pc;

Lot 4 (5?) Repair of communications

Recovery dispatch.

Installing Dispatcher consoles - 5.

(80 telephones, 60 loudspeakers, 5 boards, 5 blocks commutation);

Adjusting the assembled connection.