

<p>Repair of air conditioning and ventilation:  Replacement AC KTN-1.6m (32 pcs.)  Dismantling KTN -1.6 - 32 pcs.  Dismantling the pipeline D = 57 mm - 130 m.  Dismantling the pipeline D = 25 mm - 160 m.  Dismantling the surface of pipe insulation elastic shell - 70 m2.  Dismantling of pipe insulation mats and canvas of the super fiber - 1 m3.  Installation of KTN -1.6 - 32 pcs.  Installation of the pipeline D = 57 mm - 130 m.  Installation of the pipeline D = 25 mm - 160 m.  Installation of ball valves d = 50 mm - 10 pcs.  Installation of ball valves d = 20 mm - 64 pcs.  Installing filters d = 25 mm - 32 pcs.  Priming metal surfaces at once primed - 85 m2.  Priming metal surfaces at once lacquer - 170 m2.  Insulation mats and canvas of the super fiber - 2,6 m3.  Coating the surface of alluminum foil insulation - 160 m2.  Wrapping the surface of insulation rolled materials - 160 m2.  Shrove paint metal surfaces - 160 m2.  Descent, moving equipment materials to the installation site (2300 m) - 15,6 T.</p>	<p>Московская обл.  (в/ч 33877 ГУК)  Chekhov 3</p>
<p>Repair of air conditioning and ventilation:  Replacement AC KTN-1.6m (14 pcs.)  Dismantling KTN-1.6 - 14 pcs.  Dismantling the pipeline D = 57 mm - 270 m.  Dismantling the pipeline D = 25 mm - 95 M.4.  Dismantling the surface of pipe insulation elastic shell - 117 m2.  Dismantling of pipe insulation mats and canvas of the super fiber - 1,9 m3.  Installation of KTN -1.6 - 14 pcs.  Installation of the pipeline D = 57 mm - 270 m.  Installation of the pipeline D = 25 mm - 0,95 m.  Installation of ball valves d = 50 mm - 6 pcs.  Installation of ball valves d = 20 mm - 28 pcs.  Installing filters d = 25 mm - 14 pcs.  Priming metal surfaces at once primed - 55 m2.  Priming metal surfaces at once lacquer - 110 m2.  Insulation mats and canvas of the super fiber - 2,1 m3.  Coating the surface of alluminum foil insulation - 120 m2.  Wrapping the surface of insulation rolled materials - 120 m2.  Shrove paint metal surfaces - 120 m2.  Descent, moving equipment materials to the installation site (200 m) - 7,6 T.</p>	<p>Московская обл.  (в/ч 33877 Ц)  Chekhov 4</p>

<p>Replacing the air conditioner to-25C in the K-25SM - 2 pieces: the dismantling of the K-25C and installation of K-25SM;  replacement of pipes:  - D40mm-30m,  - D25mm-30m,  replacement ZRA:  - D 40mm, 6 pieces;  priming, painting and insulation of pipelines;  adjusting the air conditioner to-25SM. Replacement of air coolers BA-2.5 at KTH-1, 6 - 4 pcs.  dismantling of the VA-2.5  installation KTH-1, 6;  replacement of pipes d32mm-20m  replacement ZRA d-32mm 8pcs;  priming, painting and insulation of pipelines.</p>	<p>Калужская обл.  (в/ч 34080)  Ferzikovo</p>
<p>Replacing the air conditioner to-12C - 3 pcs:  dismantling of the K-12C and installation of K-12cm;  replacement of pipes d50mm - 10m,  replacement ZRA d 50mm - 6 pcs;  priming, painting and insulation of pipelines;  adjusting the air conditioner to - 12cm.  Replacing the air conditioner to-25C - 3 pcs:  dismantling of the K-25C and installation of K-25SM;  replacement of pipes d50mm - 10m,  replacement ZRA d 50mm - 6 pcs;  priming, painting and insulation of pipelines;  adjusting the air conditioner to - 25cm.</p>	<p>Калужская обл.  (в/ч 92628)  Tarusa</p>
<p>Repair and adjustment process ventilation system "C":  replacement of air coolers: the type A 53.10.2000 -01 - 2 pcs.  replacement of filters, such as FYAL-2 - 16 pcs.  replacement hermetic valves:  Type IA 01.009.1000 - 1 pc.  Type IA 01.009.300 3 pc.  Repair of total air flow and exhaust:  replacement of ducts, including:  D = 1000 - 100 m  D = 800 - 100 m  Replacing a / and / s -6.8 (4 pcs.)  Replacing the vent. aggregates 1/P1, 2/P1, 1/n2, 2/P2, 3 / 195.  Replacing hermetic valves 6/P2, 5/P1, 6/P1, 1/P1, 3/P1, 2/P1, 6 / 86.  Commissioning of ventilation. Equipment (16 pcs.)</p>	<p>г.Москва  (в/ч 25776)  Moscow</p>
<p>Replacing the air conditioner to-25C in the K-25SM - 4 pieces:  dismantling of the K-25C and installation of K-25SM;  replacement of pipes d50mm - 30m,  replacement ZRA d 50mm - 16sht.;  priming, painting and insulation of pipelines;  adjusting the air conditioner to-25SM.</p>	<p>Пензенская обл.  (в/ч 34011)  Kuznetsk 8</p>